

Intersection Improvements Main Street at South & Pine Streets


Presented by

Van Kacoyannakis, PE

August 25, 2022

Goals of Tonight's Meeting

- Review Project History
 - Assessments, Concepts, and Plans
 - Key dates
- Review Preferred Improvement Plan
 - 2020 interim striping plan
 - Shared Streets improvements
 - Final intersection design
- Discuss Next Steps
 - Public Outreach



Existing Conditions Aerial Photo



Project History: Assessments


- Planning traffic study
- Reviewed crash data
- Performed field survey
- Developed various concepts
- Identified a preferred alternative
- Implemented interim striping improvements
- Initiated State Highway coordination (Access Permit)
- Developed final plans for preferred alternative
- Pursued Shared Streets Grant (Partial Project) Awarded

Project History: Key dates

- 10/2018: Initial planning traffic study
- 5/2019: Town Meeting approved funding for preliminary design
- 5/2020: Public information meeting held to discuss project concepts
- 6/2020: Interim striping plan prepared and implemented by town at Main St/ South St/ Pine St: bicycle lanes and painted islands
- 9/2020: Project limits changed added 3 crosswalks toward Town Hall
- 3/2021: Preliminary design plans provided to the Town
- 5/2022: Shared Streets Grant awarded for 3 crosswalks
- 8/2022: Final design plans 90% complete, on hold

Project History: Roundabout Planning to Design 2018 to 2020

- 2018: Goal to design within roadway layout
 - Avoid impacts to monuments, fountains, etc.
 - Roundabout concept prepared without survey survey needed to confirm layout before MassDOT review.
- 2020: Survey completed, and design updated
 - Need to meet current MassDOT design standards
 - Deflection of entering vehicles needed to be increased
 - Splitter islands need to be raised to protect pedestrians
 - To address design requirements, impacts outside the layout would be realized







2020: Interim Plan:

Interim/ Existing Conditions



















Preferred Improvements: Final Intersection Design

- Intersection Traffic Calming
 - Narrow pavement
 - Extend curb/ replace interim painted islands with mountable decorative pavement
- Reconstruct crosswalks/ pedestrian ramps
- Provide bicycles lanes
- Design for future street lighting





Preferred Improvements: Shared Streets Grant Crosswalks

- Shift crosswalk at Elm Street
 - Move out of driveway, shift west
 - Reconstruct pedestrian ramps
- Update crosswalk at Town Hall
 - Construct raised crosswalk
 - Reconstruct pedestrian ramps
- Remove/ eliminate crosswalk to west






Main Street – Existing crosswalk to be removed, east of Pine Street



Main Street – Existing crosswalk at Town Hall, raised crosswalk



Main Street – Existing crosswalk at Elm Street to be shifted west



Preferred Improvements: Rendering on Aerial



Preferred Improvements: street view rendering comparison (existing vs. proposed)



Anticipated project construction costs (2022)

Preferred Intersection Improvements: Main Street at South & Pine Streets

Crosswalk Improvements Main Street: Shared Streets Grant (\$135,000 Awarded)

Pavement maintenance costs anticipated to be required at intersection (next 5-year)

Roundabout – (does not include property takings, reconstruction of fountain or other hardscape improvements)

~\$550,000

~\$175,000

~\$150,000

~\$ 3 Million

Note: Anticipated construction costs are office estimates, bid from contractors needed to confirm.

Project Next Steps:

- Prepared bid documents for Shared Street Grant Crosswalks:
 - Advertise project
- Public Information Meeting (Fall TBD):
 - Use this presentation for outreach meeting
 - Seek feedback from public on intersection improvements
 - Prepare handout for public to identify desired improvements:
 - 1. Do Nothing \$150,000
 - 2. Preferred Intersection Improvements \$550,000
 - 3. Roundabout \$3M
 - Evaluate feedback
 - Potentially pursue funding and approval at Town Meeting

Questions?

Van Kacoyannakis | vkacoyannakis@vhb.com | 413.241.5877

